

SCHDULE OF WORK

Name of Work ; Formation of 400 m athletic track and Cricket Pitch at NIT- T Sports ground

Ref : NITT/CoW/EMD/Civil Works/ En. No.109(118)/13-14, Dt.02.01.2014

Name of the Contractor/ Firm :

Address

SLNo	Description	Qty	Unit	Rate (Rs)	Rate(In Words)	Amount (Rs)
1	Providing, hoisting and fixing up to floor five level precast reinforced cement concrete in shelves, including setting in cement mortar 1:3 (1 cement : 3 coarse sand), cost of required centering, shuttering and finishing with neat cement punning on exposed surfaces but excluding the cost of reinforcement, with 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 12.5 mm nominal size).	16.00	cum			
2	Painting runway/taxi track/apron marking with adequate nos of coats to give uniform finish with road marking paint of superior make as approved by the Engineer-in-charge, i/c cleaning the surface of all dirt, scales, oil, grease and other foreign material etc. and lining out complete.					
2.1	New work (Two or more coats)	50.00	sqm			
3	Providing and laying sub base with sand & gravel in the proportion of 1 : 0.75 for specified thick on prepared sub grade in accordance with the requirements of the specifications. Rate includes cost of all materials to site of work, mixing in the required proportion, spreading, compacting, rolling with contractor's power roller, all labour, other incidentals etc., complete. Payment will be made only for the finished (compacted) quantum of work. (On pre level and post level measurement only).	350.00	Cum			

SLNo	Description	Qty	Unit	Rate (Rs)	Rate(In Words)	Amount (Rs)
4	Filling , spreading and levelling the available red earth in layers not exceeding 10 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift up to 1.5 m etc. complete. (Red earth will be supplied by departmentally free of cost and location will be identified by the Engineer's In charge. Payment will be made only for the finished (compacted) quantum of work. (On pre level and post level measurement only).	750	Cum			

CONTRACTOR

**SD
CHIEF OF WORKS**